

Addendum (RFP)

Addendum No: 004

Date: 11/17/2020

Project: Classroom Audiovisual Project

Project No.: WKCCD 2021-104

From: West Kern Community College District
29 Cougar Court
Taft, CA 93268

To: All Prospective Bidders and Plan Holders

The Request for Proposal issued by West Kern Community College on November 16, 2020, is hereby modified as follows:

The Infrastructure Requirements originally listed on page 8 of the RFP has been updated to remove the requirement "Upgrade UPS run time for 1 hour for all equipment to be installed". Therefore, the updated Infrastructure Requirements are listed below.

Infrastructure Requirements

- All new cabling for data will be installed according to EIA/TIA 568-B .2-10specsfor UTP Category 6 or 6a, Commercial Building Telecommunications Cabling Standard #569, Commercial Building Telecommunications Pathways and Spaces#607, and Commercial Building Grounding and Bonding Requirements for Telecommunications and any current telecommunications bulletins. Backboard layout, labeling methods, materials, and test results/methods must be approved.
- All incoming data cables going into the AV media equipment locations, need to enter through secured conduits leading them to the wire management raceways and terminated onto patch panels. Each new data cable will terminate on unloaded patch panels that accept snap in jacks similar to Allen Tel Versatap patch panels or similar models. The jacks with Category 6 or 6a wiring will terminate in District approved colored jacks. Contractor to provide and install patch panels.
- All equipment must be rack mountable.
- New Rack Cabinets, 19 in. wide rail mounts.
- Grounded patch panel type.

ALL OTHER CONDITIONS IN THE REQUEST FOR PROPOSAL REMAIN UNCHANGED